



DEPARTMENT OF PUBLIC WORKS

901 North Elm

P.O. Box 979

Rolla, MO 65402

Phone: (573) 364-8659

FAX: (573) 364-8602

e-mail: dpryor@rollacity.org

www.rollacity.org

PROJECT 582
CITY HALL REROOF
MARCH 25, 2024

ADDENDUM NO. 1

1. Where rubber pipe boots are currently present, replace with new material to match existing.
2. Remove existing sealant at reglet counter-flashings along old brick elevator shaft and install tuff stuff sealant as replacement.
3. Where existing walkway is present, remove panels before applying fluid applied system. After installation and curing of final topcoat, use CPR base coat to apply an additional coat in place of prior panels in same uniformity and dimensions. Before coating has cured, add aggregate for texture and slip resistant surface. Generic aggregate can be used at contractor's discretion.
4. Bidders shall submit bids on the attached revised Quotation Form, which must include acknowledgement of Addendum #1.

End of Addendum.



CITY HALL REROOF - PROJECT 582
CITY OF ROLLA, MISSOURI
QUOTATION FORM

The estimated quantities below are to be used as estimates only. The City of Rolla reserves the right to add or delete quantities or locations.

Includes all labor, materials, and equipment necessary for constructing all improvements as directed as shown in these specifications.

Description	Quantity	Unit Price	Extended Total
City Hall Roofing Membrane	1 LS	\$	\$
GRAND TOTAL			\$

Date _____

Address _____

Signature _____

City _____

Printed Name _____

State, Zip _____

Title _____

Phone _____

Firm _____

Fax _____

E-mail Address _____

Acknowledgement
of Addendum
No.
